ENGINEERING DEPARTMENT.

MYSORE SPECIAL DIVISION.

Notice dated 11th February 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Special Division, Mysore, up to 4th March 1929, till 12 noon for improving Adikarnataka Institute at Mysore. An abstract of approximate quantities are given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M., on the working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

4. Each tender must be accompanied by a deposit of Rs. 150 (one hundred and fifty) in cash or Government Promissory Notes, State Loan Bonds at market rates or in Savings Bank Pass Book of the tenderer having that amount at his credit on that date as earnest money, and be superscribed "Tender for improving Adikarnataka Institute at Mysore in default of which, tenders will be rejected.

5. The final acceptance of the tender will rest with the Executive Engineer, Special Division, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. No tender stating "percentage less than the lowest tender or as per estimated rates" will be accepted.

10. Once the tender has been accepted no claim for any concessions or higher rates will be entertained.

11. The work to be executed as per D. P. W. specification.

12. The decision of the Chief Engineer in all matters, regarding measurements, rates, etc., shall be final and legally binding.

ABSTRACT.

Items of work	Quantity	Per	Rate Rs.	a.	p.
I. 1. Dismantling the existing kitchen and removing debrices.	1329	C.ft.			
2. Removing old doors and windows and carting them to stores.	129	S.ft.			
3. Removing tiles and wood work of roof and carting them to stores.	8·38	Sqr.			
4. Removing the damaged Cudappah slabs flooring and carting them to stores.	2·40	,,			
II. Converting the existing dormetary into kitchen and stores —					
1. Earthwork excavation for foundation ..	2	C.yd.			
2. Burnt brick in mortar for foundation ...	42	C.ft.			
3. Burnt brick in mud superstructure ...	188	,,			
4. Removing the existing window	1	Each			
5. Chunam mortar plastering	4·00	Sqr.			
6. Removing Cudappah slabs where the wall is to be put up and refixing them after cutting them to size.	Lump	sum			
7. Refixing the available door removed from the kitchen block with required repairs and dismantling the wall.	1	Each			
8. Flooring with Vajragere 3" thick complete ...	5·80	Sqr.			
9. Unforeseen work	Lump	sum			
III. Constructing new store and fuel rooms in place of kitchen.—					
1. Earthwork excavation for foundation and filling in basement watering and tamping.	...	...			
2. Filling foundation with stone jelly concrete in chunam.	187	C.ft.			
3. Burnt brick in mortar, foundation and basement	377	,,			

	Items of work	Quantity	Per	Rate Rs.	a.	p.
4.	Burnt brick in mud superstructure ...	835	C.ft.			
5.	Teakwood wrought and put up	46·82	,,			
6.	Providing and fixing zinc sheets for valleys ...	69	S.ft.			
7.	Providing and fixing Teakwood planks ½" for valleys.	69	,,			
8.	Roofing with First Class Mangalore pattern Yelahanka tiles on teak reepers including woodoiling comple.	7·00	Sqrs.			
9.	Providing Mangalore Ridge tiles in mortar and cement pointed.	38	R.ft.			
10.	Providing mortar bands at valleys	23	,,			
11.	Providing and fixing Teak wood plain eaves board 6" deep with painting complete.	80	,,			
12.	Repairing the old available Teak wood doors ...	2	Each			
13.	Refixing windows got from dismantling ...	5	,,			
14.	Providing and fixing new Teak wood windows with iron bars, battened shutters cut into two with fittings, etc., complete.	16	S.ft.			
15.	Providing battened shutters cut into with fittings, etc., complete.	60	,,			
16.	Chunam mortar plastering	17·96	Sqrs.			
17.	Flooring with old Cadappa slabs on 3" concrete bed and cement pointing (including removing and refixing)	4·00	,,			
18.	Chacolate painting two coats	3·58	,,			
19.	White washing and other unforeseen works ...	Lump	sum			
20.	Providing and fixing 6" burnt stone slabs lintles for doors and windows roughly dressed.	50	S.ft.			
IV.	Extending the existing tormetory.—					
1.	Earthwork excavation for foundation and filling in basement watering and tamping.	35	C.yds.			
2.	Filling foundation with stone jelly concrete in chunam.	268	C.ft.			
3.	Filling foundation and basement in burnt brick in mortar.	540	,,			
4.	Superstructure in burnt brick in mud ...	1,800	,,			
5.	Providing and fixing Teakwood doors with battened shutters and fittings, etc., complete.	46	S.ft.			
6.	Providing and fixing Teakwood windows with battened shutters, Iron bars, etc., complete.	126	,,			
7.	Providing and fixing burnt stone slabs 6" roughly dressed.	62	,,			
8.	Teak wood wrought and put up	102·25	C.ft.			
9.	Providing king rod trusses as per existing design complete.	5	Each			
10.	Roofing with First Class Mangalore patern Yelahanka tiles on 2"×1" teak reepers complete.	19·07	Sqr.			
11.	Providing and fixing Mangalore ridge tiles in mortar and cement pointed.	62	R.ft.			
12.	Chunam mortar plastering	34·08	Sqr.			
13.	Flooring with Mangalore square tiles on 3" concrete bed and cement pointing complete.	12·00	,,			
14.	Painting with chacolate paint, two coats ..	16·77	,,			
15.	White washing and unforeseen charges ...	Lump	sum			
V. 1.	Providing and fixing sky light and ventilators in the central hall of the main building.	42	S.ft.			
2.	Removing the existing ventilators and carting them to stores.	4	Each			
3.	Providing and fixing steel joists with one coat of anticorrosive paint for lintles over ventilators.	8	Cwts.			
4.	Dismantling wall and terrace for inserting ventilators and sky lights and patch repairs.	Lump	sum			
5.	Providing sky lights in the rear passage ...	33	S.ft.			
6.	Providing and fixing glasses panes for the existing ones.	Lump	sum			

Items of work	Quantity	Per	Rate Rs.	a.	p.
7. Roofing with armoured glass with necessary frame work, etc., complete for both new and old one.	60	S.ft.			
8. Providing and fixing zinc sheet ridge ...	12	R.ft.			
9. Teakwood rafters for the new ones	·75	C.ft.			
10. Readjusting the slope of the terrace for the proper drainage of water on terrace.	Lump	sum			
11. Unforeseen works	Lump	sum			
VI. Constructing a new zinc sheet latrine.—					
1. Iron work	788	lbs.			
2. Providing and fixing zinc sheets with bolts and nuts.	557	S.ft.			
3. Brick in mortar	220	C.ft.			
4. Cement mortar plastering	3·60	Sqr.			
5. Providing 6" brick concrete in mortar drain with cement plaster.	40	R.ft.			
6. Flooring with 3" jelly concrete in mortar and cement plastering.	·60	Sqr.			
7. Improving the storm water drain by trimming the earthern sides and giving a proper slope for the proper discharge of water.	Lump	sum			

Abstract Notification dated 29th January 1929.

The attention of the public is invited to the notice calling for tenders for the construction of a Sandal Koti Building at Mysore, published in pages 161 and 162 of Part VI of the *Mysore Gazette*, dated 7th February 1929. The last date for receipt of tenders is 27th February 1929.

V. V. KARVE,
Executive Engineer.

KOLAR DIVISION.

Notice dated 31st January 1929.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 158 and 159, calling for tenders for restoring Singarahalli-Hongekere, Serial No. 581 of Bowringpet Taluk. Last date of tender is 25th February 1929.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 29—30th January 1929.

The attention of the public is hereby invited to the advertisement page No. 165 and 166 of the *Mysore Gazette* of calling for tenders for the constructing Police Lines at Basthihalli, Chitaldrug Taluk.

Dated 12th February 1929.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 12th March 1929, for construction of a Town Hall at Challakere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Chitaldrug between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 500 in Cash or Currency Notes, as earnest money, and be superscribed "Tender for construction of a Town Hall at Challakere" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, Shimoga Circle, Shimoga, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.